

CHEMICAL
BIDS
TO BE
OPENED

June 11, 2019
10:00 A. M.

CITY OF WESTLAKE
COUNCIL CHAMBERS
1001 MULBERRY STREET
WESTLAKE, LOUISIANA

CHEMICALS BID

**CITY OF WESTLAKE
WESTLAKE, LOUISIANA**

JUNE 11, 2019

The following is a bid for chemicals to be used in the Water Departments of the City of Westlake. Bids to be received on June 11, 2019, at 10:00 A.M. in the City Council Chambers located at 1001 Mulberry Street, Westlake, Louisiana. Sealed bids may be turned in to the City Clerk at the above address between the hours of 9:00 A.M. and 4:00 P.M., Monday through Thursday, and up until 10:00 A.M. on June 11, 2019.

The bid amount specified is for a twelve month supply. Beginning July 1, 2019 through June 30, 2020. Bid prices should include any delivery and/or storage costs as well as any other charges (i.e. cylinder charges). See Exhibit "A" for other specifications. Chemicals are to be delivered as needed and transferred into our system as specified by the Public Works Director and/or Water Superintendent. Prices should not include any sales tax as the City is totally exempt from any sales tax.

1. AQUA-MAG (C&L 723L) LINEAR CHAIN PHOSPHATE	4527 GALS. (50973 LBS.)	\$ _____	Total \$ _____/lbs
2. CARRUS-MFT POTASSIUM PERMANGANAGE OR AMERICAN MADE EQUIVALENT	3850 LBS.	\$ _____	Total \$ _____/lbs
3. CHLORINE (150# CYLINDERS)	2400 LBS.	\$ _____	Total \$ _____/lbs
TOTAL BID:		\$ _____	

BIDDER: _____

STREET AND/OR BOX: _____

CITY/STATE: _____

CONTACT PERSON: _____

TITLE: _____

PHONE NUMBER: _____

EMAIL ADDRESS: _____

SIGNATURE: _____

DATE: _____

EXHIBIT "A"
SPECIFICATIONS

Bid must include the following Chemical Storage Tanks:

Chemical - Orthophosphate

Hilma Street Location:

Horizontal 300 Gallon w/bottom
Feed Outlet w/valve
Graduations marked in gallons
5' long x 3' diameter

Shady Lane Location:

Vertical 160 Gallon w/pump
Mount on top of tank
Graduations marked in gallons
66" high x 29" diameter

NOTE: MUST BE ABLE TO SEE LEVEL FROM OUTSIDE THE TANK. BOTH TANKS MUST BE TOP LOAD.

CONTRACTOR QUALIFICATIONS:

- Supplier must be a contractor, or have a dedicated division, in the business of supplying water treatment products (chemicals and equipment) and services for the control of corrosion, deposition, and biological control in water utility systems. The Contractor will have technical support for its field staff.

REPRESENTATIVE QUALIFICATIONS:

- The Contractor will designate a primary representative and a support technician and will provide telephone, voicemail, and email contact information for each.
- Each of these contacts must be a certified water technician, and have a minimum of ten years field experience in water treatment. The contractor will provide documentation of this certification and experience.
- The Contractor's primary representative will reside within two hours of the City of Westlake, Louisiana and be able to respond on-site within two hours notification. The support technician is exempt from these requirements.

- Documentation of these requirements will be required prior to final award of a contract.

SPECIFICATIONS:

- All supplied chemicals must be National Sanitation Foundation (NSF) certified.
- Contractor will make monthly site inspections to all locations, as scheduled by OWNER.
- During each monthly inspection, the Contractor will test orthophosphate and (TKPP) levels on all applicable operation wells.
- During each monthly inspection, the Contractor will log orthophosphate and (TKPP) inventory levels.
- The Contractor will provide twelve (12) scheduled site inspections per year.
- The Contractor will review log data and inventory since last visit with OWNER's representative.
- The Contractor will review and address customer generated questions and issues concerning the testing.
- The Contractor will maintain sufficient on-site inventories to insure continuous operation at acceptable treatment levels.
- The Contractor will conduct water and pipe sample tests and metallurgical analysis for quality control and problem solving.
- The Contractor will provide third party, off-site lab testing.
- The Contractor will schedule all site inspections with City representative a minimum of forty eight (48) hours before desired inspection time.